

ATTENTION ALL BIDDERS:

The following changes are hereby made to the Contract Bidding Documents for this project:

GENERAL CLARIFICATIONS:

1. Project Budget is \$425,000 to \$450,000
2. The Abatement Contractor shall cover fixed walls all the way up to the ceiling in the Auditorium with two (2) layers of four (4) mil polyethylene sheeting to the floor level. Once the areas in the Auditorium has cleared all PCBs verification sampling, the Abatement Contractor shall remove and dispose of the first layer of (4) mil polyethylene sheeting, and leave intact the second layer of (4) mil polyethylene sheeting. The Abatement Contractor shall repair any holes or tears to the second layer of (4) mil polyethylene sheeting that might be created during the removal of the first layer of (4) mil polyethylene sheeting
3. Bidders can view PDF's of the documents at www.merrittgraphics.com, log into planwell.

EQUAL OR SUBSTITUTIONS:

None

SPECIFICATIONS:

None

DRAWINGS:

1. AD-100: Hatched area with Key Note Q at exterior of building adjacent to Door 8 should be Key Note H
2. A-100: Band Room 407, Existing Fixed Instrument Storage Closet in front of new door 407 shall be shifted to corner where existing door 08 was.